




CITY OF MASON

**MASON WTP FILTER BACKWASH, FORCE MAIN
AND AERATOR CONTACT BASIN**

CONTRACT NO. 5E

**CHANGE ORDER
NO. 5E-1**

CONTRACT CHANGE ORDER		Date: March 5, 2002	
		Project: Mason WTP, Filter Backwash, Force Main, and Aerator Contact Basin	
		Location: Mason Water Treatment Plant	
To (Contractor): O.R.E. Electric 5110 Webster Street Dayton, OH 45414		Contract No.: 5E	
		Change Order No. 5E-1	
You are hereby requested to comply with the following changes from the contract plans and specifications:			
Item No. (1)	Description of changes - quantities, units, unit prices, change in completion schedule, etc. (2)	Decrease in contract price (3)	Increase in contract price (4)
1	Heat Trace of Exposed Pipe: Extra heat trace system on pipe exterior exposed pipe. See Attachment No. 1		\$ 10,733.00
	Change in contract price due to this Change Order:		
	Total decrease:	\$0.00	
	Total increase:	XXXXXXXXXX	\$ 10,733.00
	Difference between column (3) and (4):	XXXXXXXXXX	\$ 10,733.00
	Net <u>increase</u> in contract price:	XXXXXXXXXX	\$ 10,733.00
This change <u>increases</u> the total contract price, and the total adjusted contract price to date thereby is \$ <u>107,056.00</u> .			
The time provided for completion in the contract for the above items is <u>increased</u> by <u>0</u> calendar days. This document shall become an amendment to the contract and all provisions of the contract will apply hereto.			
Accepted by <u></u> Contractor		<u>3-6-02</u> Date	
Recommended by <u></u> Architect/Engineer		<u>3-7-02</u> Date	
Approved by <u></u> Owner		<u>3/31/02</u> Date	

**CITY OF MASON
MASON WTP FILTER BACKWASH, FORCE MAIN
AND AERATOR CONTACT BASIN
CONTRACT NO. 5E**

CHANGE ORDER NO. 5E-1

ITEM AND DESCRIPTION

1. At the Aerator Contact Basin (ACB) heat trace the exterior exposed 4" drain line on the east side of the ACB and the exterior exposed 20" RWS line on the west side and top of the ACB. Use an existing conduit and pull boxes running between the ACB and MCC-12. Seal all openings in boxes. Temporary power will be required until the existing Aerators are shutdown and the existing conduit system is available.

Provide heat trace system per Specification Section 16672 for the exposed lines to 4' below grade of the vertical pipe. See Attachment No. 1.

REASON FOR CHANGE

1. The heat trace system and pipe insulation for certain exterior pipelines were not included in the original contract. Heat trace exterior exposed pipe under the pipe insulation to prevent freezing.